

# Local Notice to Mariners

## Position Correction to NtM 2024 – 055

### Darwin Ship-lift project - Turbidity buoy positions

<b>To</b>	Port Users	<b>Location</b>	Darwin Ship-lift Construction Site
<b>Date of issue</b>	23 August 2024	<b>Ref number</b>	Local NtM 2024/068 (T)

## Notification

Deployment of turbidity buoys for the Darwin ship lift project	
<b>Date of activity:</b>	2 August 2024
<b>Time of activity:</b>	2 August 2025
<b>Location of activity:</b>	Darwin Ship-lift site, see attached diagram
<b>Assets/ Vessels involved</b>	MV Houtman
<b>Description of Activity:</b>	Two Turbidity buoys are to be placed in the following locations: 1) Lat. 12° 29. 6083 S. 130° 53. 7463 E (SE Dredge Extent) in 4m 2) Lat. 12° 29. 4755 S. 130° 54. 1541 E (SW Dredge Extent) in 3-5m  The buoy will be Yellow in colour with Lt. Fl. 1s ON, 3s Off, and anchored by 500Kg Delta Flipper anchor's, 6m length of 13mm marine chain swivel, 12mm FSWR connecting to buoy.
<b>Conducted by:</b>	Bhagwan Marine Pty Ltd
<b>Communication : Radio</b>	VHF Channels: 16 & 76
<b>Mobile</b>	Brendan Pilmore-0401003281 ShaneElstone-0429370210
<b>Additional information</b>	
<b>Cancel this notice on:</b>	To be informed

Jon Abbey

A / Regional Harbourmaster – Darwin

## Turbidity Buoy Locations:



---