



Construction Notes

- Permitted clearing area digital line-work to be obtained from DLRM
- Contractor to inspect and flag all constraints and clearing areas prior to commencement of works
- Clearing Area 1: 64ha
- Clearing Area 2: 67ha
- Existing clearing on property: 175ha
- Total clearing property: 306ha (32.55% of total property area)
- All boundary buffers 110m wide
- Wildlife corridor 100m wide
- Buffer along creek 100m from the edge of the primary bank
- 100m buffer from the edge of sinkhole
- 100m buffer between proposed clearing areas
- Slope in clearing areas maximum 2%
- Graded bank to be surveyed and constructed in Clearing Area 1
- All ripping, mounding and ploughing to be done across the slope
- Improved pasture species to be planted: Sabi, Buffel, Jarra and Cavalcade

Contacts

Site Manager: John Smith ph: 0400 000 000
 Contractor: Smith Dozers ph: 0411 111 111
 Property Owners: Gillard & Co ph: 0422 222 222
 DLRM: ph: (08) 8973 8838

Legend

- Sinkhole
- Cycad Creek
- ➔ Direction of Slope
- Contours (2m interval)
- Graded bank
- ▭ Property Boundary
- ▭ Vegetation Buffer 100m
- ▭ Clearing - Proposed
- ▭ Clearing - Existing

Data Source

Boundary/Contours:
Dept Lands Planning Environment
© Northern Territory of Australia
Background Image: Google Earth - date

Erosion and Sediment Control Plan

Date: 26/02/2014
Drawing No: ESCP-001

NT Portion 1234
101 Territory Rd, Katherine
Proposed Clearing Areas
Overview